

SEWAGE PUMPS

Electrical Data: **SWH300**

MODEL	HP	HZ	VOLTS/ PH	RPM	FULL LOAD AMPS	NEMA START CODE	CORD TYPE	CORD SIZE	CORD O.D.	POTENTIAL RELAY	START CAPACITOR	RUN CAPACITOR
SWH300M2-20	3	60	230/1	1750	28.0	D	SOW	8AWG/4C	1.0	CONTINUOUS COIL MIN VOLTAGE: 350V PICK-UP MAX: 200V DROP OUT MAX: 75V	750UF±5%-220 VAC	40UF±5%-370VAC
SWH300M3-20	3	60	230/3	1750	16.0	D	SOW	12AWG/4C	.7	N/A	N/A	N/A
SWH300M4-20	3	60	460/3	1750	8.0	D	SOW	12AWG/4C	.7	N/A	N/A	N/A
SWH300M5-20	3	60	208/1	1750	35.5	D	SOW	8AWG/4C	1.0	USMR-50-LF ICM CONTROLS 50 AMP RELAY	750UF±5%-220 VAC	40UF±5%-370VAC
SWH300M6-20	3	60	208/3	1750	18.0	D	SOW	12AWG/4C	.7	N/A	N/A	N/A

ELECTRICAL DATA:

R.P.M.	1750
MOTOR TYPE	CAPACITOR START/CAPACITOR RUN (1PH) INDUCTION (3PH)
GEN INSULATION CLASS	B
WINDING INSULATION TEMP	130°C
VOLTAGE TOLERANCE	±10%



P U M P

Honest, Professional, Dependable

1191 Commerce Parkway, Ashland, Ohio 44805
Telephone: 855 281-6830 • Fax: 877 326-1994 • ashlandpump.com